# Exterior Renovation Estimate

Design: Design A · Project 146dcf6e · 05 Nov 2026



Original



Redesigned

## Selected materials

| Material | Applied to | Durability & upkeep |
|---|---|---|
| Window Frame – uPVC, White | window | Frame and sash with hardware, priced per sq ft of window opening; sealant and fixing in the preparation rate. |
| Exterior Emulsion – Warm Cream | balcony | Weatherproof exterior emulsion, primer plus 2 coats (about 50 sq ft per litre on rough plaster). Repaint every 5-7 years. |
| Railing – Aluminium, Black | railing | Priced per running foot, supplied and fixed. Measured along the longest edge of each railing (or balcony). |
| MS Gate – Brown | gate | Mild-steel gate with primer and powder coat or enamel; priced per sq ft of gate. Repaint every 4-5 years near the coast. |
| Window Glass – Clear 6 mm | window | Toughened glass priced per sq ft of glazed area (85% of the window opening). |

## Quantities and cost

| Material | Measured | Order quantity | Material | Preparation | Labour | Total |
|---|---|---|---|---|---|---|
| Window Frame – uPVC, White | 952.8 sq ft | 952.8 sq ft | ₹3,62,064 | ₹11,434 | ₹66,696 | ₹4,40,193 |
| Exterior Emulsion – Warm Cream | 367.7 sq ft | 7.8 L (+5% wastage) | ₹3,510 | ₹2,574 | ₹5,147 | ₹11,231 |
| Railing – Aluminium, Black | 180.3 rft | 185.7 rft (+3% wastage) | ₹1,29,990 | ₹9,017 | ₹36,067 | ₹1,75,073 |
| MS Gate – Brown | 696.6 sq ft | 696.6 sq ft | ₹3,13,470 | ₹17,414 | ₹41,793 | ₹3,72,677 |
| Window Glass – Clear 6 mm | 809.9 sq ft | 834.2 sq ft (+3% wastage) | ₹75,078 | ₹4,049 | ₹20,247 | ₹99,374 |

## Cost by category

| Category | Material | Labour | Total |
|---|---|---|---|
| Window Frames | ₹3,73,498 | ₹66,696 | ₹4,40,193 |
| Paint | ₹6,084 | ₹5,147 | ₹11,231 |
| Railings | ₹1,39,007 | ₹36,067 | ₹1,75,073 |
| Gates | ₹3,30,884 | ₹41,793 | ₹3,72,677 |
| Glass | ₹79,127 | ₹20,247 | ₹99,374 |
| **Grand total** | **₹9,28,599** | **₹1,69,950** | **₹10,98,549** |

Likely range given measurement uncertainty: ₹9,46,364 – ₹12,49,742

## How these numbers were derived

• Each surface is calibrated from a reference rectangle of known real size marked on the photo; pixel areas are converted to square feet from it.
• Overlapping regions are resolved so openings (windows, doors) and railings are excluded from wall areas.
• Ranges reflect the uncertainty from placing the reference corners (about ±2 px). Photo perspective and surfaces at a different depth add error.
• Order quantity = measured area × (1 + wastage) ÷ coverage per unit (paint per litre, tiles per piece); other materials are bought by the sq ft or running foot.
• Cost = order quantity × material rate + measured area × preparation rate (primer, putty, adhesive, fixings) + measured area × labour rate. Wastage is paid for in material only.
• Rates are editable planning assumptions in INR, not quotations. This estimate is advisory and not legally binding; confirm with your contractor.