Exterior Renovation Estimate

Design: Design A · Project 4defc0b3 · 05 Nov 2026



Original



Redesigned

Selected materials

Material	Applied to	Durability & upkeep
Exterior Emulsion – Sage Green	wall	Weatherproof exterior emulsion, primer plus 2 coats (about 50 sq ft per litre on rough plaster). Repaint every 5-7 years.
Window Frame – Aluminium, Black	window	Frame and sash with hardware, priced per sq ft of window opening; sealant and fixing in the preparation rate.
Door – Oak Veneer Flush	door	Priced per sq ft of door, shutter and frame together. Finish and polish are in the preparation rate.

Quantities and cost

Material	Measured	Order quantity	Material	Preparation	Labour	Total
Exterior Emulsion – Sage Green	1,302.6 sq ft	27.4 L (+5% wastage)	₹12,330	₹9,119	₹18,237	₹39,686
Window Frame – Aluminium, Black	346.4 sq ft	346.4 sq ft	₹2,14,768	₹4,156	₹24,246	₹2,43,170
Door – Oak Veneer Flush	153.1 sq ft	153.1 sq ft	₹1,37,790	₹6,125	₹15,312	₹1,59,226

Cost by category

Category	Material	Labour	Total
Paint	₹21,449	₹18,237	₹39,686

Category	Material	Labour	Total
Window Frames	₹2,18,924	₹24,246	₹2,43,170
Doors	₹1,43,915	₹15,312	₹1,59,226
Grand total	**₹3,84,288**	**₹57,795**	**₹4,42,082**

Likely range given measurement uncertainty: ₹3,75,770 – ₹5,08,395

How these numbers were derived

• Each surface is calibrated from a reference rectangle of known real size marked on the photo; pixel areas are converted to square feet from it.
• Overlapping regions are resolved so openings (windows, doors) and railings are excluded from wall areas.
• Ranges reflect the uncertainty from placing the reference corners (about ±2 px). Photo perspective and surfaces at a different depth add error.
• Order quantity = measured area × (1 + wastage) ÷ coverage per unit (paint per litre, tiles per piece); other materials are bought by the sq ft or running foot.
• Cost = order quantity × material rate + measured area × preparation rate (primer, putty, adhesive, fixings) + measured area × labour rate. Wastage is paid for in material only.
• Rates are editable planning assumptions in INR, not quotations. This estimate is advisory and not legally binding; confirm with your contractor.