Exterior Renovation Estimate

Design: Design A · Project 146dcf6e · 05 Nov 2026



Original



Redesigned

Selected materials

Material	Applied to	Durability & upkeep
Window Frame – uPVC, White	window	Frame and sash with hardware, priced per sq ft of window opening; sealant and fixing in the preparation rate.
Exterior Emulsion – Warm Cream	balcony	Weatherproof exterior emulsion, primer plus 2 coats (about 50 sq ft per litre on rough plaster). Repaint every 5-7 years.
Railing – Aluminium, Black	railing	Priced per running foot, supplied and fixed. Measured along the longest edge of each railing (or balcony).
MS Gate – Brown	gate	Mild-steel gate with primer and powder coat or enamel; priced per sq ft of gate. Repaint every 4-5 years near the coast.
Window Glass – Clear 6 mm	window	Toughened glass priced per sq ft of glazed area (85% of the window opening).

Quantities and cost

Material	Measured	Order quantity	Material	Preparation	Labour	Total
Window Frame – uPVC, White	197.0 sq ft	197.0 sq ft	₹74,860	₹2,364	₹13,791	₹91,015
Exterior Emulsion – Warm Cream	76.0 sq ft	1.6 L (+5% wastage)	₹720	₹532	₹1,064	₹2,316
Railing – Aluminium, Black	82.0 rft	84.5 rft (+3% wastage)	₹59,150	₹4,100	₹16,400	₹79,650
MS Gate – Brown	144.0 sq ft	144.0 sq ft	₹64,800	₹3,601	₹8,642	₹77,043
Window Glass – Clear 6 mm	167.5 sq ft	172.5 sq ft (+3% wastage)	₹15,525	₹837	₹4,187	₹20,549

Cost by category

Category	Material + preparation	Labour	Total
Window Frames	₹77,224	₹13,791	₹91,015
Paint	₹1,252	₹1,064	₹2,316
Railings	₹63,250	₹16,400	₹79,650
Gates	₹68,401	₹8,642	₹77,043
Glass	₹16,362	₹4,187	₹20,549
Grand total	**₹2,26,489**	**₹44,084**	**₹2,70,573**

Likely range given measurement uncertainty: ₹2,35,718 – ₹3,04,977

How these numbers were derived

• Each surface is calibrated from a reference rectangle of known real size marked on the photo; pixel areas are converted to square feet from it.
• Overlapping regions are resolved so openings (windows, doors) and railings are excluded from wall areas.
• Ranges reflect the uncertainty from placing the reference corners (about ±2 px). Photo perspective and surfaces at a different depth add error.
• Order quantity = measured area × (1 + wastage) ÷ coverage per unit (paint per litre, tiles per piece); other materials are bought by the sq ft or running foot.
• Cost = order quantity × material rate + measured area × preparation rate (primer, putty, adhesive, fixings) + measured area × labour rate. Wastage is paid for in material only.
• Rates are editable planning assumptions in INR, not quotations. This estimate is advisory and not legally binding; confirm with your contractor.